

*Copy*

265 M

# ENGINEERING MEMORANDUM

BRISTOL AIRCRAFT (WESTERN) LIMITED  
WINNIPEG CANADA

TITLE  
REPAIR SCHEME  
ELEVATOR BELLCRANK

E.M. NO. 12362  
EFFECTIVE AS DEC'D  
DWG. NO.

FILE CODE  
111  
-A1

PART NAME  
186138 BELLCRANK

JOB NO.  
CUSTOMER'S ORDER NO.  
CUSTOMER  
RC AF

COPIES TO  
6

USE OF E.M.	DISPOSITION OF STOCK			
	CHECK BLOCKS AFFECTED	NOT AFFECTED	REWORK	AS NOTED
SALVAGE	<input checked="" type="checkbox"/>			
CONCESSION				
STOP ORDER/RELEASE				
NEW DRAWING				
REVISED DRAWING				
VARIATION				
OBSCLETE NOTICE				
USE AS NOTED				

ORIGINATED BY  
BREWER

TYPE AIRCRAFT  
N.D. Brewster

AIRCRAFT REGISTRATION NO.  
606 H.H.K.

DATE  
15/1/57

DWG. CHANGE  
YES

APPROVALS  
*[Signature]*  
ENGINEERING

CONTRACT ADMIN.  
*[Signature]*  
CUSTOMER

GIVE FULL PARTICULARS AND SKETCH WHERE POSSIBLE

ELONGATED HOLES AS SHOWN ON SHEET WILL BE REPAIRED AS FOLLOWS:

1. REAM EXISTING HOLES AS SHOWN
2. MANUFACTURE BUSHINGS.
3. INSTALL BUSHINGS WET WITH ZINC CHROMATE PRIMER TO MIL-P-6889.
4. CLEAN OUT SLOTS AFTER INSTALLATION.

NOTE: 2 BUSHINGS REQ'D FOR EITHER ~~A~~ OR ~~B~~

*[Signature]* 19  
*[Signature]*  
*[Signature]*

SEP 16 1958

*[Handwritten notes and signatures at the bottom of the page]*



# ENGINEERING MEMORANDUM

TITLE

REPAIR SCHEME  
ELEVATOR BELLCRANK

E.M. NO.

12362




# ENGINEERING MEMORANDUM

TITLE

REPAIR SCHEME  
ELEVATOR BELLCRANK

E.M. NO.

17362



MTL: SAE 4130 TO MIL-S-6758  
CAD PLATE TO QQ-A-416 TYPE  
I CLASS 2 - DIMS TO BE MET AFTER  
PLATING

BUSH FOR

A

BUSH FOR

B


# ENGINEERING MEMORANDUM

TITLE

REPAIR SCHEME  
ELEVATOR BELLCRANK


E.M. NO.

12362



REPAIR AT "B-B"

REPAIR AT "B-B"



REPAIR AT "A-A"

REPAIR AT "A-A"